

Aidan Levy | Ben Tipper-Shaw Ryan Muir | Jacob Budgell





Department of Civil Engineering Group 6

South Bar Small Craft Harbour Design


Introduction & Project Scope

Project Location: South Bar, Cape Breton, Nova Scotia

Project Overview: Lobster fishing harbour facility redesign and consolidation.

Reason for Redesign:

Replacement of aging structures. Future maintenance deemed more costly than new construction.



Locational Earth & Environment Study

Research Sections:

- Wind/Wave Study
- Tides/Ice
- Bathymetry
- Geology (Bedrock & Top-soil)
- Surrounding Topography
- Local Resources

Wave Climate Design Process

Predominant Wind Speeds and Directions

- MSC50 Climactic Data
- Development of Wind Rose

Site Specific Wave Influence Factors

- Fetch limited or fully developed waves
- Protection from northern sea swell

Development of Design Wave Parameters


- Wave rose developed for onshore conditions
- Wave Transformations


On Shore Wave Conditions

- Wave Height: 1.4m
- Wave Period: 4s
- Wave Direction: 60° (NNW)

Local Geology:

- Sandstone (~200kPa bearing)
- Topsoil: Stony Sand Till






Tidal Range, Sea Level Rise & Ice Conditions

- Highest Water Line: 3.6m
- Ice Thickness: 70cm To 120cm
- Tidal Range: 1.5m
- 100yr. Sea-Level Rise: 1.2m

Proposed Design

Features:

- Rubble-Mound Breakwater
- Sheet-Pile Marginal Wharf
- Floating Wharf Berthing (16 Lobster boats + more)
- Slipway
- Harbour Master's Office
- Trap Laydown Area
- Parking lot



Rubble-Mound Breakwater

Design Layers:

- 1.02m diameter armour stone layer.
- 0.5m and 0.17m diameter underlayers.
- 0.045m diameter core.
- 2m x 2m toes using 0.5m diameter stones.
- 2.2m freeboard.

Stage

Site Prep

Breakwater

Marginal Wharf

Floating Wharf

Other Amenities

Total (\$)

Extra

Safety

Insurance & Bonds

Inflation

Contingency

Total

Engineering & Geotechnical 10

—Steel Sheet pile

• 4m crest

PRIMARY ARMOUR 1.858m THICK FIRST UNDERLAYER 0.86m THICK SECOND UNDERLAYER 0.3177m THICK ∑ CORE SEAWARD LEEWARD Sea Level Rise

r 200mm reinforced concrete slab

10mm compacted gravel

concrete deadman

1inch hot dip galvanized with epoxy coating

Cost

\$183,000

\$6,360,000

\$1,010,000

\$136,000

\$260,000

Unit

3 %/yr.

\$4,411,695

2.5 %

Cost


\$7,949,000

1000mm compacted quarry stone

compacted reclaimed fill


Steel Sheet-pile Marginal Wharf

Steel sheet-pile retaining wall with cathodic protection, supported by concrete dead-man anchors @ 2m o.c., surfaced with a 200mm slabon-grade designed for impact loading. Backed with compacted gravel, quarry stone, and reclaimed local stony sand till.



Grand Total: \$12.4M + \$1.85M (HST)

Timeline Management




- Total Project Timeline: 274 Days
- Key Timeline Factors:
- Total Time
- Resource Allocation/Mgmt.
- Fishing Season (August-Mid-October)
- Start: Nov. 4, 2021; End: July 3, 2022

Resource/Service Allocation - Timeline management by consideration of services and associated costs and coordination therein.

- Labour Crews (Concrete or Other trades)
- Equipment schedules:
- Dump trucks
- Excavators
- Roller-Compactor
- Services Provided (Concrete pumps/delivery)

Dump Truck Resource Allocation Timeline



Key References

- Introduction to Coastal Engineering and Management Kamphius (2019) $3^{\rm rd}$ ed.
- The Rock Manual CIRIA (2007)
- Coastal Engineering Manual US Army Corps of Engineers (2006)
- Harbour Accommodations Guidelines Public Works Canada (2015)

Acknowledgements

Group 6 would like to extend our thanks to our academic and industry advisors Dr. Mysore Satish (Dal.), Danker Kolijn (CBCL), as well as course coordinators Dr. Yi Liu and Dr. Craig Lake for providing guidance, support and the necessary tools to successfully complete our project.